## BOARD OF ARCHITECTURAL REVIEW AGENDA July 16, 2015 - 4:00 PM Council Chambers - Rouss City Hall

## 1. POINTS OF ORDER

- A. Roll Call
- B. Approval of Minutes July 2, 2015

## 2. CONSENT AGENDA

## 3. **NEW BUSINESS**

**BAR-15-358** Request of Kyle Hopkins for a Certificate of Appropriateness to build a board fence and plant buffer at 502 Fairmont Avenue.

**BAR 15-368** Request of Martha Shickle for a Certificate of Appropriateness to re-roof 219 South Kent Street.

**BAR 15-374** Request of Benjamin Butler for a Certificate of Appropriateness to replace windows at 234 Amherst Street.

## 4. OLD BUSINESS

## 5. OTHER DISCUSSION

## 6. ADJOURN

\*\*\*APPLICANT OR REPRESENTATIVE MUST BE PRESENT AT THE MEETING\*\*\*

## BOARD OF ARCHITECTURAL REVIEW MINUTES

The Board of Architectural Review held its regularly scheduled meeting on Thursday, July 2, 2015, at 4:00p.m. in Council Chambers, Rouss City Hall, 15 North Cameron Street, Winchester, Virginia.

### POINTS OF ORDER:

PRESENT: Chairman Rockwood, Vice Chairman Bandyke, Mr. Serafin, Mr. Walker, Ms. Elgin,

Ms. Schroth

ABSENT: Ms. Jackson

STAFF: Josh Crump, Aaron Grisdale, Carolyn Barrett
VISITORS: Robina Bouffault, Kathy Lewis, Cheryl Anderson

## **APPROVAL OF MINUTES:**

Chairman Rockwood called for corrections or additions to the minutes of June 18, 2015. Mr. Walker asked for a correction to BAR-15-336. Voice vote was taken and the minutes passed as amended 6-0.

### **CONSENT AGENDA:**

None

### **NEW BUSINESS:**

**BAR-15-196 & BAR-15-347** Request of 309 BRAD LLC for a Certificate of Appropriateness for a partial demo/adaptive reuse of an old warehouse to residential at 309 North Braddock Street.

Ms. Bouffault spoke about the progress made in the demolition of the building. The remainder of the building that was partially demolished was not structurally sound enough to keep. She reviewed the new plan and materials that will be used for a new home.

## **Chairman Rockwood Opened the Public Hearing**

## **Chairman Rockwood Closed the Public Hearing**

Chairman Rockwood read the criteria from Winchester Zoning Ordinance Chapter 14-6-2 concerning demolition of historic buildings. He stated the building did not meet any of the qualifications set forth in the city ordinance therefore there was no reason to deny the certificate.

Vice Chairman Bandyke made a motion to grant a Certificate of Appropriateness to **BAR-15-347** for the demolition of the building as proposed. Mr. Serafin seconded the motion. Voice vote was taken and the motion passed 6-0.

Ms. Bouffault reviewed the changes and revised materials to the second part of her request. Mr. Serafin asked about the eight inches of CMU that will be left. Ms. Bouffault said they would probably parge it because concrete block is porous.

Mr. Walker made a motion to grant a Certificate of Appropriateness to **BAR-15-196** with the addition that the exposed CMU left after the demolition be parged, otherwise as submitted. Mr. Serafin seconded the motion. Voice vote was taken and the motion passed 6-0.

**BAR-15-359** Request of Kathy Lewis, Red Fox Creamery, for a Certificate of Appropriateness for a service window at 4 West Cork Street.

Ms. Lewis described the serving window that had been installed. Chairman Rockwood said the new window was vinyl. Ms. Lewis said her carpenter had told her it was wood. Chairman Rockwood said he had touched it and verified it was vinyl. Ms. Lewis said she would have it redone but had hoped to open her business for the 4<sup>th</sup> of July celebrations. Chairman Rockwood said she would be able to open but needed to change the window after the 4<sup>th</sup> of July.

Vice Chairman Bandyke made a motion to grant a Certificate of Appropriateness to **BAR-15-359** to install a sliding service window that is made out of wood, full-view, no mullions and white.

## **OLD BUSINESS:**

**BAR-15-304** Request of Cheryl Anderson for a Certificate of Appropriateness to remodel the façade at 118-120 North Loudoun Street, the Winchester Hiram Lodge.

Ms. Anderson described the interior remodel she has been working on. She has removed layers of drywall and framing to get down to the brick walls. Drop ceilings have also been removed revealing ceiling medallions. She is proposing to go back to the original brickwork on the exterior by removing the metalwork from the front of the building. She has permission from the Masons to remove the metalwork.

Vice Chairman Bandyke said removing the metal would be an improvement. If the awning could be removed, that would be an improvement as well. Mr. Serafin said the tricky part would be if the surface underneath was a disaster. He recommended that if there are problems, she come back with improvements or changes after seeing what is there. Ms. Anderson said it will be done the right way. She has been researching the correct materials to use. The board members said they need to see what she is going to propose after seeing what is underneath the metalwork.

Ms. Schroth asked if the Bell's store wanted the metal removed from their façade. Ms. Anderson said they are waiting to see what she finds underneath 116 North Loudoun Street. They may elect to leave it as is.

Mr. Serafin made a motion to grant a Certificate of Appropriateness to **BAR-15-304** for removal of the existing metal siding. Any additions are to come back with another application. Vice Chairman Bandyke seconded the motion. Voice vote was taken and the motion passed 6-0.

### **DISCUSSION:**

Vice Chairman Bandyke mentioned overgrown trees hanging over the sidewalk on Braddock Street.

## **ADJOURN:**

With no further business before the Board, the meeting was adjourned at 4:31pm.

CERTIFICATE #: BAR- 15-35%
DATE SUBMITTED: 6/22/15





Rouss City Hall 15 North Cameron Street Winchester, VA 22601

Telephone:

(540) 667-1815

FAX: TDD: (540) 722-3618

TDD: (540) 722-0782 Web: www.winchesterva.gov

(form updated 02/06/15)


## APPLICATION BOARD OF ARCHITECTURAL REVIEW CERTIFICATE OF ARRESONATEMESS

	CERTIFICATE OF APPRO	<b>DPRIATENESS</b>		
Please print or type all information:		KYLE HOPKING		
	•	Applicant		
540 550 5458		502 FAIRMONT AVE		
Telephone		Street Address		
Kyleshopkins@email E-mail address	com	WINCHESTER VA 22601		
E-mail address		City / State / Zip		
N/ I				
Property Owner's Signa		Property Owner (Name as appears in Land Records)		
	ature	. 12		
SAME AS ABOVE Telephone		SAME		
• 1552 -		Street Address		
SATEAS ABOVE E-mail address		City / State / Zip		
		City / State / Zip		
Zoning: (HW) Year Construct  TYPE OF REQUEST  Demolition	Sign (specify type) and #	Historic Plaque? Y N Number:		
New Construction	Freestanding	Siding		
Addition	Wall	Roofing		
Fence/Wall	Projecting	☐Windows/Doors		
CONCEPTUAL REVIEW ONLY	Other sign (specify)	Paint		
Other (specify)				
***SEE REVERSI	FOR MATERIALS TO INC	CLUDE WITH APPLICATION***		
FOR OFFICE USE ONLY				
BAR Review OR Administra	tive Review per Section 14-5			
Hearing Date(s)	30000124			
CERTIFICATE OF APPROPRIATENESS:	APPROVED DISAPPRO	VED TABLED WITHDRAWN		
CONDITIONS NOTED:				
SIGNATURE:		DATE:		
Secretary, Boar	d of Architectural Review			

## **APPLICATION - BOARD OF ARCHITECTURAL REVIEW**

FOR ALL APPLICATIONS:
The Board of Architectural Review (BAR) uses the following when considering applications:
The Secretary of Interior's Standards for Rehabilitation www.nps.gov/tps/standards/rehabilitation/rehab
Winchester Historic District Guidelines www.winchesterva.gov/planning/historic-district-design-guidelines
Article 14 of the Winchester Zoning Ordinance www.winchesterva.gov/planning/zoneord
Applicants should carefully review their proposal relative to these guiding documents prior to submission. In
addition to the required materials listed below, applicants are encouraged to provide a narrative description of
the scope of the project and how it relates to these documents.
The BAR meets at 4pm on the first and third Thursdays of each month in Council Chambers.
The deadline for COMPLETE applications (inc. all required materials) is 5pm ten (10) days before the meeting.
The applicant or a representative must be at the meeting to answer any questions the Board may have and to
discuss any possible changes or suggestions.
Some applications may be considered for administrative review and approval per Section 14-5 of the Zoning
Ordinance; however, all applications must include all required materials as if referred to the BAR.
All projects must also comply with all applicable ordinances and building codes.
***ALL APPLICATIONS <u>REQUIRE</u> A RECENT PHOTOGRAPH (10 copies) OF THE STRUCTURE OR PROPERTY TO BE ALTERED; plus:
SIGN APPLICATIONS, REQUIRED MATERIALS: (***10 copies of each)
Scaled drawing showing materials used, colors, lettering style, and type (if any) of illumination.
Sketch/clear description of where sign will be located. Include clearance for any projecting signs.
For freestanding signs, scaled site drawing showing sign placement.
PAINT COLOR CHANGE, REQUIRED MATERIALS: (***10 copies of each)
☐ Samples of paint colors. (Give careful consideration to appropriateness of colors to age and style of structure.)
A clear description of what will be painted, including trim, window frames, railing, gutters, porch floors/ceilings, etc.
NEW CONSTRUCTION, ADDITIONS, REMODELING OR RENOVATIONS, WALLS/FENCES, REQUIRED MATERIALS:  (***10 copies of each)
Detailed sketch/architectural rendering and construction plans of additions and new construction.
Samples, descriptive brochures and details of ALL materials.
Scaled site plan for new construction, additions, walls and fences.
walls and reflects.
ROOFING, REQUIRED MATERIALS: (***10 copies of each)
Samples of materials, style and color of proposed roof.
DEMOLITION, REQUIRED MATERIALS:
Photographs of all sides of structure/feature to be demolished. (***10 copies of each)
For structures or portions of structures over 75 years old, \$300.00 filing fee. Such application requires a public hearing per Section 14-3-2 of the Zoning Ordinance; additional time between filing and the hearing may be
required in order to satisfy procedural requirements for public positions of said basels

NOTE: AN APPROVED CERTIFICATE OF APPROPRIATENESS EXPIRES TWELVE (12) MONTHS FROM THE DATE OF ISSUANCE OR OTHERWISE AS PROVIDED FOR IN SECTION 14-8 OF THE ZONING ORIDINANCE.





Size of typical neighboring lots




Size of 502 Fairmont Ave (.90 Acre)



Site hazards



Site Limitations





Existing front yard fences within 2 blocks




















Existing front yard fences within 2 blocks





Existing front yard fences within 2 blocks




-proposed fence detail



1x6 painted boards

4x4 wooden posts with 1x4 wooden cap


8'-0'








-proposed gate detail





## CITY OF WINCHESTER ---

Address: 502 Fairmont Avenue Present Use: Residential
Map & Parcel: 153-(1)  Tract & Block: 3-38  Assessed Value: 548,125
Present Owner: J. Lee Miller Address:  Historic Name: Original Owner: Original Use:
Date: 17_ 80 90 1800 10 20 30 40 50 60 70 80 90 1900 19_
Style: (Vern) L.Geor. Grk.Rev. Ital. 2ndEmp. Rom. Goth. Q.A. Col.Rev. B.Arts None+ None-
Stories: B 1 $1\frac{1}{2}$ 2 $(2\frac{1}{2})$ 3 $3\frac{1}{2}$ 4
Material: Stone Log Clapbrd. Wd.Fr. (Brk.) Plas. Brick
Modifications: Minor Moderate Extensive
Physical Condition: Standard Deteriorated Dilapidated
Environmental Context: Strong Moderate Weak
Architectural Significance: - Outstanding Excellent Good Average None Architectural Description
Outstanding Excellent Good Average None
Outstanding (Excellent Good Average None Architectural Description  This rambling house in a modified Greek cross plan is well-sited on a rocky hill at the corner of Fairmont and North Avenues. The dominant feature is the bracketed porch which wraps around three sides of the house. Other features are the shingled and bracketed gable projections, with palladian style windows, the bracketed and dentiled cornice, the two-story three sided hay front and the parameter.
Outstanding (Excellent Good Average None Architectural Description  This rambling house in a modified Greek cross plan is well-sited on a rocky hill at the corner of Fairmont and North Avenues. The dominant feature is the bracketed porch which wraps around three sides of the house. Other features are the shingled and bracketed gable projections, with palladian style windows, the bracketed and dentiled cornice, the two-story three sided bay front and the parapet along the roof crest.  Historical Significance: National State/Regional Local None
Outstanding (Excellent Good Average None Architectural Description  This rambling house in a modified Greek cross plan is well-sited on a rocky hill at the corner of Fairmont and North Avenues. The dominant feature is the bracketed porch which wraps around three sides of the house. Other features are the shingled and bracketed gable projections, with palladian style windows, the bracketed and dentiled cornice, the two-story three sided bay front and the parapet along the roof crest.  Historical Significance: National State/Regional Local None
Outstanding (Excellent Good Average None Architectural Description  This rambling house in a modified Greek cross plan is well-sited on a rocky hill at the corner of Fairmont and North Avenues. The dominant feature is the bracketed porch which wraps around three sides of the house. Other features are the shingled and bracketed gable projections, with palladian style windows, the bracketed and dentiled cornice, the two-story three sided bay front and the parapet along the roof crest.  Historical Significance: National State/Regional Local None
Outstanding (Excellent Good Average None Architectural Description  This rambling house in a modified Greek cross plan is well-sited on a rocky hill at the corner of Fairmont and North Avenues. The dominant feature is the bracketed porch which wraps around three sides of the house. Other features are the shingled and bracketed gable projections, with palladian style windows, the bracketed and dentiled cornice, the two-story three sided bay front and the parapet along the roof crest.  Historical Significance: National State/Regional Local None

References:





## **502 Fairmont Avenue**

Tax Map Number: 153-1-8-38-DHR Resource Number: 138-0042-0459


Resources: 1 single dwelling; 1 prefabricated shed

Date/Period: ca. 1900 Style: Queen Anne

Sources: Sanborn Fire Insurance Company Maps; Quarles, The Story of

One Hundred Old Homes

## **Architectural Description**



**Secondary Resource Summary:** A one-story prefabricated shed is located near the northern boundary of the property and is sited directly north of the dwelling.

Primary Resource Description: Constructed circa 1900, this two-and-one-half-story single-family dwelling was influenced by the Queen Anne style. Set on a solid foundation of random rubble, this building is faced with stretcher-bond brick. The dwelling is primarily capped by a front-gabled roof and features multiple projecting gables; all covered with slate shingles. A molded cornice with dentils and scrolled modillions accents the roof. A central-interior brick chimney pierces the ridge of the roof and has a corbeled cap. A second interior brick chimney, with recessed panels, marks the northern slope of the roof and has a corbeled cap. The central bay of the façade (west elevation) holds a single-light, wood-frame glass door and is surmounted by a single-light transformance and a wood lintel. The northernmost bay of the façade holds a single-leaf fixed wood window, which is topped by a stained glass transom and a wood lintel. The northernmost bay of the second story holds paired 1/1, double-hung, wood-sash windows. A three-sided, canted bay projects from the southernmost bay of the façade and rises the full height of the dwelling. The bay has the same material treatment as the main block and is capable by half-himself participation of the dwelling. The bay has the same material treatment as the full height of the dwelling. The bay has the same material treatment as the full height of the dwelling. The bay has the same material treatment as the full height of the dwelling. The bay has the same material treatment as the full height of the former to the full height of the dwelling. The bay has the same material treatment as the full height of the former to the full height of hipped roof (material not visible). Fenestration consists of 1/1, double-hung, wood-sash windows. The tympanum of the facade is clad with square-butt wood shingles and is pierced by triple 1/1, double-hung, wood-sash windows. A wood lintel surmounts the opening and is topped by a semi-circular sunburst panel. All windows on the façade feature a wood sill and lintel. A one-story, wraparound porch, with a rounded southwest corner, spans the facade and extends two bays along both the north and south (side) elevations. The porch is set on a brick pier foundation with wood lattice infill and is capped by a half-hipped roof. Standing-seam metal covers the roof, which is supported by Tuscan wood columns. Turned wood balusters complete the porch, which is accessed via a flight of wooden steps in the central bay. The south and north (side) elevations are fenestrated with 1/1, double-hung, wood-sash windows. Each window opening has a wood sill and lintel. A two-story, three-sided canted bay rises along the south elevation and is set on a random rubble foundation. The bay has the same material treatment as the main block and is capped by a half-hipped roof. Fenestration consists of 1/1, double-hung, wood-sash windows. Each window has a wood sill and lintel. A gable rises above the bay and has a roof covered with slate shingles. The tympanum is clad with square-butt wood shingles and is pierced by a 1/1, double-hung, wood-sash window with a pedimented surround. A three-sided rectangular bay rises the full height of the north elevation and is capped by a gabled roof of slate shingles. The bay has the same material treatment as the main block and features a tympanum clad with square-butt wood shingles. Visible fenestration consists of single and paired 1/1, double-hung, wood-sash windows. Each window opening has a wood sill and lintel.

A two-story ell extends from the northernmost bay of the rear (east) elevation and is original. The ell has the same material treatment as the main block and is capped by a front-gabled roof of slate shingles. Cornice returns, dentil molding, and scrolled modillions, finish the roof. The upper gable end is clad with weatherboard wood siding. An interior-end paneled brick chimney rises from the east elevation and has a corbeled cap. Fenestration consists of a single-leaf, paneled wood door with lights and 1/1, double-hung, wood-sash windows. Each window opening has a wood sill and lintel. A one-story appendage extends from the north elevation of the ell and is original. The appendage has the same material treatment as the main block and is capped by a half-hipped roof (material not visible). Visible fenestration consists of 1/1, double-hung, wood-sash windows. A two-story porch is located on the south elevation of the ell and is also original. The porch is set on a wood post foundation and is capped by a half-hipped roof of standing-seam metal. Square wood posts support the second story and the roof. Square wood balusters encircle the second story of the porch.

**Secondary Resource Description:** A one-story, one-bay prefabricated shed, constructed circa 2000, is located north of the dwelling. The wood-frame shed is clad with standing-seam metal and is capped by a gabled roof. The shed was not visible from the public right-of-way due to trees and foliage.

Significance Statement: This single-family dwelling is a distinctive example of the domestic architecture constructed along Fairmont Avenue in the City of Winchester during the early twentieth century. Influenced by the Queen Anne style, this single-family dwelling is sited on a prominent elevated lot at the intersection of Fairmont Avenue and West North Avenue. Judging by the form and materials of the dwelling, as well as by using Sanborn Fire Insurance maps, this dwelling can be given a circa 1900 date of construction. This building retains integrity of materials, workmanship, and design. Further, it retains integrity of location and setting. All of these aspects contribute to integrity of feeling and association. This single-family dwelling is a contributing resource to the Winchester Historic District under Criteria A and C.



CERTIFICATE #: BAR- 15-368 DATE SUBMITTED: 6/29/15



OF WINCERSON

Rouss City Hall 15 North Cameron Street Winchester, VA 22601 Telephone: (540) 667-1815 FAX: (540) 722-3618 TDD: (540) 722-0782 Web: www.winchesterva.gov

## APPLICATION BOARD OF ARCHITECTURAL REVIEW CERTIFICATE OF APPROPRIATENESS

	CERTIFICATE OF APPRO			
Please print or type all information:		Martha Shichle Applicant		
<u>Б40 334 [323</u> Telephone		219 South Kent Street Street Address		
Shickleism@g Mail.com E-mail/address		City / State / Zip		
Mart Sul Property Owner's Signature		Martha F. Shickle Property Owner (Name as appears in Land Records)		
540 336 132	3	219 South Kent St		
Telephone		Street Address		
Shickle is M@g	Maul. com	Winchester VA 22601		
E-mail addres	S	City / State / Zip		
Zoning: HRL (HW) Year Const		Historic Plaque? Y( ✔ N( ) Number:		
☐ Demolition	☐ Sign (specify type) and #	Exterior Change		
□ New Construction	☐ Freestanding	☐ Siding		
Addition	□ Wall	Roofing		
☐ Fence/Wall	Projecting	☐ Windows/Doors		
CONCEPTUAL REVIEW ONLY	☐ Other sign (specify)	□ Paint		
☐ Other (specify)				
***SEE REVER	SE FOR MATERIALS TO INC	CLUDE WITH APPLICATION***		
FOR OFFICE USE ONLY				
BAR Review OR Adminis	trative Review per Section 14-5			
Hearing Date(s)				
CERTIFICATE OF APPROPRIATENESS:	☐ APPROVED ☐ DISAPPRO	VED TABLED WITHDRAWN		
CONDITIONS NOTED:				
SIGNATURE:		DATE:		
	oard of Architectural Review	VAIL.		



## CITY OF WINCHESTER ARCHITECTURAL INVENTORY

Address: 219 South Kent Street	Present Use: Residential
Map & Parcel: 193-(1) Tract & Block: Q-15	Assessed Value: \$7,950
Present Owner: Irene Va. Hodgson Address:	Historic Name: Original Owner: Original Use:
/\ <sub>t</sub>	
Date: 17_ 80 90 1800 10 20 30 40	50 60 70 80 90 1900 19
Style: Vern. L.Geor. Grk.Rev. Ital. 2 B.Arts None+ None-	
Stories: B 1 (1) 2 2 2 3 3	4
Material: Stone (Log Clapbrd. Wd.	German
Modifications: (Minor) Moderate Ex	ctensive
Physical Condition: (Standard Deterior Environmental Context: Strong Moderat	_
J	

Architectural Significance:
Outstanding (Excellent Good Average None
Architectural Description


This three bay log house is attractively sited on the corner lot. Distinguishing features are the large outside right end chimney with a later brick hood addition, the one-story shed wing to the right and the rear ell with entrance on Clifford Street and large outside chimney. The house has four over four lights on the first floor, six over six in the dormer windows and nine over nine in the gable window. The V-shaped decorative siding on the dormer probably is a later addition. The Victorian 4-paneled door has segmental windows in the upper two panels. There is a

pleasant entrance porch with turned rosts and sawn calusters.

Historical Significance:
National State/Regional Local None

Historical Description

References:





## 219 South Kent Street

Tax Map Number: 193-1-Q- 15-


DHR Resource Number: 138-0042-0539

Resources: 1 single dwelling Date/Period: ca. 1800 Style: Vernacular

Sources: Sanborn Fire Insurance Company Maps; Quarles, The Story of

One Hundred Old Homes

## **Architectural Description**



Secondary Resource Summary: There are no visible secondary resources associated with this property.

**Primary Resource Description**: This one-and-a-half-story, three-bay single dwelling is set on a solid foundation of uncoursed stone. The log dwelling is clad with German wood siding and has wood corner boards. A large exterior-end, brick chimney with an arched hood rises from the side (north) elevation. The side-gabled roof is covered with square-butt wood shingles and features two front-gabled dormers. The dormers are clad with diagonally placed, beaded wood siding and contain 6/6, double-hung, wood-sash windows with narrow wood surrounds. A one-story, three-bay porch stretches across the façade. Set on a brick pier foundation, the porch has a balustrade with sawn balusters and a half-hipped roof of standing-seam metal that is supported by turned wood posts. The window openings on the façade contain 2/2, double-hung, wood-sash windows with narrow wood surrounds and operable, louvered wood shutters. A single-leaf, paneled wood door with narrow, half-round lights pierces the center bay of the façade. The side (south) elevation is fenestrated by a 6/6, double-hung, wood-sash window in the upper gable end.

A one-story addition is located on the rear (west) elevation of the main block. Set on a coursed stone foundation, the addition is clad with German wood siding and has a front-gabled roof of standing-seam metal. An exterior-end, brick chimney with a metal hood rises from the rear (west) elevation. This addition is noted on the 1885 Sanborn Fire Insurance map, the first year that this area was recorded.

A one-story, full-depth addition, probably log construction, is located on the side (north) elevation. This addition has a shed roof and the same material treatment as the main block. A recessed, single-leaf door of vertical boards provides entry into this addition from South Kent Street. It is reached by concrete steps.

A one-story addition is located on the side (north) elevation of the first addition. Clad with German wood siding and set on a solid concrete foundation, the addition has a shed roof covered with standing-seam metal. Fenestration consists of two fixed, six-light wood windows on the east elevation.

A one-story, one-bay porch, on the south elevation of this addition, is set on a brick pier foundation. A set of side-entry concrete steps provide access to the porch. The single-leaf entry has a paneled wood door with lights. The porch has a sawn wood balustrade and a half-hipped roof of standing-seam metal that is supported by chamfered wood posts. This addition is fenestrated with 2/2, double-hung, wood-sash windows with narrow wood surround and operable, louvered wood shutters.

A one-story, shed-roofed addition has enclosed the north elevation of the rear addition. It is clad with German wood siding.

A one-story porch is located on the north elevation of the shed-roofed addition and has a shed roof supported by square wood posts.

**Significance Statement:** This single-family dwelling is representative of the domestic architecture constructed in the City of Winchester at the turn of the eighteenth century. It is one of the oldest extant domestic buildings on South Kent Street, and in the Winchester Historic District, and maintains its integrity of feeling because it evokes a sense of its historic time period. The dwelling retains its integrity of materials, workmanship, although additions have weakened its integrity of design. However, the additions are modest and relegated to the side and rear elevations of the main block. The integrity of location and setting has been maintained. All of these aspects contribute to integrity of feeling and association. The dwelling retains sufficient integrity to qualify under Criteria A and C as a contributing resource in the Winchester Historic District.







Rouss City Hall 15 North Cameron Street Winchester, VA 22601

Telephone:

(540) 667-1815

FAX:

(540) 722-3618

TDD:

(540) 722-0782 Web: www.winchesterva.gov

## **APPLICATION BOARD OF ARCHITECTURAL REVIEW**

	CERTIFICATE OF APP	PROPRIATENESS	
Please print or type all information:		Benjamin	M. Butler
540-662-34	86	234 Am	nenst St
Telephone		Stre	eet Address
E-mail address	ucast Net	Winches	tery VA 22601
E-mail address	1	City /	State / Zip
Jan R.	Butler		
Property Owner's Signa		Property Owner (Nam	e as appears in Land Records)
	965	234 /4	mherst St
bmb/Aw 1 @ C on	and wat	Stre	eet Address
E-mail address	CAST. NEI	City /	<u> </u>
Zoning: (HW) Year Construc	ted:	Historic Plaque?	Y( ) N( Number:
Demolition	Sign (specify type) and #	Exterior	Change
New Construction	Freestanding	Sidi	ng
Addition	Wall	Roc	fing
Fence/Wall	Projecting	Wir	dows/Doors
CONCEPTUAL REVIEW ONLY	Other sign (specify)	Pair	nt
Other (specify)			
***SEE REVERSE	FOR MATERIALS TO	INCLUDE WITH APPL	ICATION***
FOR OFFICE USE ONLY			
BAR Review OR Administrat	ive Review per Section 14-5		
Hearing Date(s)			
CERTIFICATE OF APPROPRIATENESS:	APPROVED DISAPP	ROVED TABLED	WITHDRAWN
CONDITIONS NOTED:		W 150-57	
SIGNATURE:			
	d of Architectural Review		





Customer Information

me: BENJAMIN BUTLER

ddress: 234 AMHERST ST

WINCHESTER, VA 22601

rimary Phone: 540-247-4144

Secondary Phone: 540-247-4144

WINCHESTER
2350 LEGGE BLVD
WINCHESTER, VA 22601

Store Number: 4618

Dustomer Agreement#; 258260

ssociate: SEAN

5

100-1

Ver. 50

44.5 x 62 None Facing

Installation Zip Code = 22601

U.S. ENERGY STAR® Climate Zone = North

Central

Standard Width = Custom

Standard Height = Custom

Frame Width = 44 1/2

Double-Hung

Frame Height = 62

Frame Option = No Flange

Unit Sill Angle = 8 Degrees - Moderate

Frame Depth = 4 9/16"

Venting / Handing = AA

Exterior Color = White

Exterior Sash/Panel Color = White

Interior Species = Pine

Interior Finish Color = White - Painted

Glass Option = Low-E4 SmartSun

High Altitude Breather Tubes = No

Glass Strength = Standard

Glass Tint = No Tint

Specialty Glass = None

Hardware = None

Hardware Style = Traditional

Lock Hardware Style = Traditional

Number of Sash Locks = 2

Lock Hardware Color = White

Full Divided Light (FDL)

Specified Equal Light

Grille Pattern = Specified Equal Light

Grille Bar Width = 7/8"

Exterior Grille Color = White

Interior Grille Species = Pine

Interior Grille Color = White

4W2H

Insect Screen Type = None

Extension Jamb Type = None

Stool Option = None

Room Location = Living Room

Search by Unit Code = No

Unit U-Factor = 0.3

Unit Solar Heat Gain Coefficient (SHGC) = 0.18

U.S. ENERGY STAR Certified = Yes

Limited Travel = No

SKU = 290211

Vendor Name = S/O ANDERSEN LOGISTICS

Vendor Number = 60509030


Customer Service = (888) 888-7020

Catalog Version Date = 4/17/2015

N: E \* L u

W

2



Unit U-Factor = 0.3

Limited Travel = No SKU = 290211

Vendor Number = 60509030

Unit Solar Heat Gain Coefficient (SHGC) = 0.18

Vendor Name = S/O ANDERSEN LOGISTICS

U.S. ENERGY STAR Certified = Yes

Customer Service = (888) 888-7020 Catalog Version Date = 4/17/2015 j

5

## CITY OF WINCHESTER ARCHITECTURAL INVENTORY

ARCH					11	PIS 1 104-7 9/		125
Address:	234 Am	herst			.,			7
Map & Pa		72 - (1)						100
Present C Address:	wner:	Alda L.	& Claude	e Cammer				1 L S - C
Present L	lse: res	idence			C C C C C C C C C C C C C C C C C C C			2
Assessed Historic (	l Value: Name:	\$77 <b>.</b> 975	5	w s		35	100 m	
Original	Owner:	6			ž.	Trimeiae Paggar		1
Original I	Use:	a		88 F	ŀ			A.
Date: 1	7 80	90 18	00 10 20	30 40 5	50 60 70	80 90 190	0 1925-	<del>.</del> ح
Style: V	ern. L.	Geor. Gr None+ N	k.Rev. I	tal. Emp	Rom. G	oth. Q.A.	Col.Rev	
Stories:	B 1	1 2	] 2 <del>1</del>	3 3 <del>1</del>	4 _		_	
Material:	Stone	Log [	Clapbrd.	Wd.F1	. Brk.	Plas.		
Modificati	ons: · M	lnor	Moderate	Exte	ngive			
Environme Architectu	ntal Cont	ext: St	rong M	teriorat oderate	.ed Dil	None	stural Dece-'-	4:
Environme Architectu Our The st	ral Signif tstandir	icance: Exce	rong M	teriorat oderate Good	Weak Average	None Architec	etural Descrip e length er of the	_ 4
Environme Architectu Ou The st	ral Signif tstandir one wal	icance: Exce	rong M	teriorat oderate Good	Weak Average	None Architec	0 30m=+h	
Environme Architectu Ou The st	ral Signif tstandir one wal	icance: Exce	rong M	teriorat oderate Good	Weak Average	None Architec	0 30m=+h	_ 4
Architectu Ou: The st the bl neighb	ral Signif tstandir one wallock con orbood.	ext: St icance: ig Exce l and br tribute	ick pavito the s	teriorat oderate Good	Weak Average	None Architec	0 30m=+la	of
Architectu Ou: The st the bl neighb	ral Signif tstandir one wallock con orbood.	icance: Exce	ick pavito the s	teriorat oderate Good	Weak Average	None Architectinued th 1 charact	e length er of the	of
Architectu Ou: The st the bl neighb	ral Signif tstandir one wallock con orbood.	ext: St icance: ig Exce l and br tribute	ick pavito the s	teriorate  Good  ng which trong re	Weak  Average  are conesidentia	None Architectinued th 1 charact	e length er of the	of
Architectu Ou: The st the bl neighb	ral Signif tstandir one wallock con orbood.	ext: St icance: ig Exce l and br tribute	ick pavito the s	teriorate  Good  ng which trong re	Weak  Average  are conesidentia	None Architectinued th 1 charact	e length er of the	of
Architectu Ou: The st the bl neighb	ral Signif tstandir one wallock con orbood.	ext: St icance: ig Exce l and br tribute	ick pavito the s	teriorate  Good  ng which trong re	Weak  Average  are conesidentia	None Architectinued th 1 charact	e length er of the Na Na	of
Architectu Ou: The st the bl neighb	ral Signif tstandir one wallock con orbood.	ext: St icance: ig Exce l and br tribute	ick pavito the s	teriorate  Good  ng which trong re	Weak  Average  are conesidentia	None Architectinued th 1 charact	e length er of the Na Na	of
Architectu Ou: The st the bl neighb	ral Signif tstandir one wallock con orbood.	ext: St icance: ig Exce l and br tribute	ick pavito the s	teriorate  Good  ng which trong re	Weak  Average  are conesidentia	None Architectinued th 1 charact	e length er of the Na Na	of

ก



## 234 Amherst Street

Tax Map Number: 172-1-8-6-


DHR Resource Number: 138-0042-0007 Resources: 1 single dwelling; 1 garage

Date/Period: ca. 1930 Style: Colonial Revival

Sources: Sanborn Fire Insurance Company Maps; Quarles, The Story

of One Hundred Old Homes

## **Architectural Description**



Secondary Resource Summary: There are no visible secondary resources associated with this property.

**Primary Resource Description:** This two-story, three-bay, single-family dwelling was constructed circa 1930 in the Colonial Revival style. Set on a solid foundation of coursed rubble stone, the dwelling is clad in wood weatherboard. The building is capped with a side-gable roof covered in standing-seam metal, embellished with a boxed wood cornice that is obscured by an aluminum gutter. An exterior-end chimney rises at the east elevation, it is random rubble stone capped with a metal hood.

The symmetrical façade is marked by a central entry, flanked by a window to each side, with a window centered in each bay of the second story above. The central entry is set beneath a one-story, one-bay porch, set under a half-hipped roof of standing seam metal, embellished with an overhanging cornice and frieze panel, and supported by Tuscan wood columns. Approached by a set of stone steps, its foundation is not visible from the public right-of-way The entry beneath is marked by a single-leaf paneled wood door with four-light sidelights set in a wood ogee surround. Each window at the façade is 8/8 double-hung wood sash, set in a square-edged wood surround and flanked by operable louvered wood shutters.

The east elevation of the dwelling is marked by a full-height rectangular projecting bay at its north bay. Set on a stone foundation, it is capped with a side-gable pedimented roof, covered in standing seam metal. It is fenestrated with single, paired and tripled 1/1, double-hung vinyl sash windows, and with typical 8/8 wood windows, each flanked by inoperable louvered wood shutters. The south bay of the east elevation of the main building is visible: it is fenestrated with a single, typical 8/8 window with operable shutters at its first and second stories. The west elevation of the dwelling is marked by a full-height, rectangular bay projection at its southernmost bay. The projecting bay is set on a stone foundation, and is capped with a flat roof (material not visible). Its fenestration is obscured by shrubbery. The west elevation of the main block is fenestrated with 6/6 and 8/8 double-hung wood windows; each is set in a square-edged wood surround with wood sill, flanked by inoperable louvered wood shutters. The upper gable end is fenestrated with paired, double-hung windows, material not visible, flanked by inoperable shutters. A square vent is set above in the upper gable end.

A two-story addition set under a shed roof extends across the full width of the rear (north) elevation of the building; its details are not visible from the public right-of-way. A small, one-story, gable-end ell addition extends from its westernmost bay, its details are not visible from the public right-of-way. A larger, one-story, gable end addition extends from the rear (north) elevation of the smaller gable addition. It is constructed of concrete block, and sits under a roof of standing-seam metal; fenestration and other details are not visible from the public right-of-way.

**Secondary Resources Description:** This one-story, two-bay garage, constructed circa 1960, is located at the northeast corner of the property, at the end of the asphalt driveway leading from Amherst Street. Set under a front-gable roof (material not visible), the garage is clad in weatherboard; its foundation is not visible. Its south elevation is marked by large paneled wood with lights doors.

**Significance Statement:** This two-story, single-family dwelling is indicative of domestic architecture constructed in the City of Winchester in the second quarter of the twentieth century. Based on its form and materials and also by using Sanborn maps, the building can be given a circa 1930 date of construction. The Colonial Revival-style single-family dwelling retains integrity of materials, workmanship, and design. The rear additions to the dwelling do not compromise its integrity. Further, this dwelling retains integrity of location and setting. All of these aspects contribute to integrity of feeling and association. This single dwelling is a contributing resource to the Winchester Historic District under Criteria A and C.

